

# Commissioning of the SNS Beam Instrumentation



**Tom Shea**

**for the SNS Diagnostics Team**

**Oak Ridge National Laboratory (ORNL), Oak Ridge, TN, USA**

# The Spallation Neutron Source Partnership




The SNS will begin operation in 2006

At 1.4 MW it will be ~8x ISIS, the world's leading pulsed spallation source  
5000 hours per year at an availability of >90% ..... (~ in 2009)

# Accelerator Overview


## Now Commissioned to 158 MeV through CCL



1 RFQ  
6 DTL Tanks  
4 CCL Modules

11 Medium- $\beta$  Cryomodules - 3 Nb cavities each  
12 High- $\beta$  Cryomodules - 4 Nb cavities each

Proton energy on target	1.0 GeV
Power on target	1.4 MW
Pulse repetition rate	60 Hz
Macro-pulse length	1 ms
Ave. current in macro-pulse	26 mA
H <sup>-</sup> peak current front end	> 38 mA
Peak current in ring	52 A
Proton pulse width on tgt	695 ns
Energy per Pulse	>17 kJ
Uncontrolled beam loss	<1 W/m



# Commissioning runs in parallel with installation



- Run #1:** - RFQ at LBNL (2.5 MeV), Jan 25th through Feb 2002  
- beam stop for design beam power
- Run #2:** - Front End at LBNL (2.5 MeV), Apr 4 to May 31, 2002  
- beam stop for design beam power
- Run #3:** - Front End at ORNL (2.5 MeV), Nov 5, 2002 to Jan 31, 2003  
- beam stop for design beam power
- Run #4:** - Front End, DTL tank 1, D-Plate (7.5 MeV), Aug 26 to Nov 17, 2003  
- beam stop and radiation shield for design beam power
- Run #5:** - Front End & DTL tank 1,2,3 (39 MeV) Spring 2004  
- Beam stop and radiation shield for reduced beam power (50us, 1Hz)
- Run #6 :** - Front End, DTL, CCL modules 1,2,3 (158 MeV) Fall 2004  
- Beam stop and radiation shield for reduced beam power (50us, 1Hz)
- Run #7 :** - Front End, DTL, CCL, SCL (1 GeV), Fall 2005
- Run #8 :** - Front End, DTL, CCL, SCL, Ring (1 GeV), Early 2006
- Run #9 :** - Front End, DTL, CCL , SCL, Ring, Target (1 GeV), by June 30, 2006

# RFQ at Berkeley - 2 Diagnostic Devices

## Commissioning: Jan 25<sup>th</sup> through Feb 2002



1


2002

2003

2004

2005

2006





8 mA transmitted on first pulse, 24 mA current on first day

Emittance integrated with controls, all else via scopes

### RFQ

- 1 Emittance (one plane)
- 1 Faraday Cup (scope)





# RFQ Commissioning at LBNL

## Emittance

Vertical: 0.325 pi mm mrad (design goal: 0.3 pi mm mrad)

Distribution has about 1% floor most likely due to scattering (not emittance in this case)



# Front End at Berkeley - 16 Devices

## April 4, 2002 to May 31, 2002




- MEBT**
- 6 Position
  - 2 Current
  - 5 Wires
  - 1 Laser (test)
  - 1 Emittance (One Plane)

All diagnostic systems were prototypes of linac systems


Integrated with EPICS via portable channel access

All integrated at LBNL within one week and delivered useful information for commissioning



# Carbon Wire Scanners



- This case: 20 mA debunched beam
- Compare measured rms transverse beam size to Trace3D simulation
- Virtually all measurements agree with model to within 10%, mc within 5%





# Beam Position Monitors

## Position met spec; Phase was not quite there




Channel Access




Electrodes - LBNL


Cables & install - LBNL



Electronics, NAD software - LANL




# Laser Photo-neutralization of H- Ions



Calculated cross section for H- photoneutralization as a function of photon wavelength.\*

Nd:YAG laser has  $\lambda=1064\text{nm}$  where the cross section is about 90% of the maximum.

\*J.T. Broad and W.P. Reinhardt, Phys. Rev. A14 (6) (1976) 2159.





- Scan laser transversely across ion beam
- Plot one of the following vs. laser beam position:
  - Missing current in H- beam
  - Collected electrons liberated from H- beam

# Transverse Profiles measured with Laser at LBNL

First measurement of SNS beam with by laser photo-neutralization

Small Nd YAG laser system provided by BNL and installed at LBNL, measurements performed by ORNL

Amplitude of missing beam current plotted vs Scanning mirror position



# FE/MEBT at ORNL = 19 Devices


## Nov 5, 2002 through Jan 31, 2003



- MEBT**
- 6 Position
  - 2 Current
  - 5 Wires
  - 2 Neutron
  - 1 Emittance Horizontal
  - 1 Fast Faraday Cup
  - 1 SCL Laser

Test of SCL laser system, gap measurement

Based on LBNL experience, added neutron detectors (first borrowed from LBNL, then part of INR collaboration)




# Front End at ORNL – Jan 2003

## Laser Profile Monitor Results at 2.5 MeV



- Verification of **electron collection** for SCL laser profile monitor
- Reliable measurements to about **3 sigma**
- Anti-reflection coating for final windows.
  - May measure well beyond 3 sigma.





### Horizontal Profile

1/25/2003 13:06

Gaussian fit plotted out to 2.5x Sigma

Sigma = 1.07 mm



### Signal from electron collector

Top: laser intercepting beam core

Bottom: laser intercepting beam tail

# Through DTL Tank 1/D-Plate: 31 Devices

## August 26 through Nov 17, 2003



**MEBT**

- 6 Position
- 2 Current
- 5 Wires
- 2 Thermal Neutron
- 1 Fast Faraday Cup
- 1 Faraday/Beam Stop
- Differential BCM

**DTL/D-Plate**


- 2 Position
- 1 Current
- 2 Wire
- 7 Ion Chamber
- 4 Thermal
- 3 Semi
- 2 Faraday Cup
- 1 Bunch
- 1 Video
- 1 Halo
- 3 Neutron
- 1 Beam Stop
- Faraday Cup
- 1 Emittance (Slit and Collector)
- Differential BCM

last run at full power until beam on target

Diff BCM (analog)


Test BSM

Migration to EPICS IOC core, structured LabVIEW



# DTL Faraday Cup

- First beam through DTL-1 Tank was seen on console in control room.



Typical Faraday Cup (energy degrader removed)

# Commissioning through first 3 (of 6) DTL Tanks: 54 Diagnostic Devices




D-plate removed

Added D-box to MEBT for inline emittance and others

Improved phase performance of all BPMs

- MEBT**
- 6 Position
  - 2 Current
  - 5 Wires
  - 2 Thermal Neutron
  - 1 Emittance Horizontal
  - 1 Emittance Vertical
  - 1 Faraday/Beam Stop
  - D-box emittance
  - D-box beam stop
  - D-box aperture
  - Differential BCM

- DTL**
- 5 Position    3 Wire
  - 3 Faraday Cup    3 Current
  - 7 Loss Ion Chamber    Differential BCM
  - 4 Thermal    3 Semiconductor





# BPM delivers Position and Phase


## DTL3 Results Pulse-to-Pulse Phase Jitter




LLRF Goal: 0.5 degrees (at 402.5 MHz)

Measurements as low as 0.1 degrees at 805 MHz (0.05 deg @ 402.5) indicate that BPM/Phase diagnostics are meeting spec (also validates new LLRF systems)

Histogram of measured beam phase with respect to RF reference




# CCL commissioning: 136 Devices



- MEBT**
- 6 Position
  - 2 Current
  - 5 Wires
  - 2 Thermal Neutron
  - 1 Emittance Horizontal
  - 1 Emittance Vertical
  - 1 Mode-locked Laser
  - 1 Faraday/Beam Stop
  - D-box emittance
  - D-box beam stop
  - D-box aperture
  - Differential BCM

- CCL**
- 10 Position 9 Wire
  - 8 Neutron, 3 BSM,
  - 2 Thermal
  - 28 Loss 3 Bunch
  - 1 Faraday Cup 1 Current
  - 1 Dump





- DTL**
- 10 Position 5 Wire 12 Loss
  - 5 Faraday Cup 6 Current
  - 6 Thermal and 12 PMT Neutron
  - Differential BCM



Tools to support large scale deployment: database configuration control, Altiris, Windows XP, collaboration with IT

Migrate to fiber distribution of Diagnostics RF reference


# Position and loss measurements through CCL




Beam loss distribution along the linac. Raw data with beam on (left), no beam (center), With beam on and subtracted background (right). Now integrated with machine protect system.

# Difference orbit through CCL first try

## Model vs measurements




# Difference orbit after correcting integrated field values in model




L3; NEW LATTICE: DTL6-CCL3; NEW LATTICE: DTL6-CCL3; NEW LATTICE: DTL6-CCL3; NEW LATTICE: DTL6-CCL3; NEW LATTICE: DTL6-CCL3; NEW LATTICE: DTL6-CCL3

# Effect of beam loading in the Linac Bunch Shape Monitor results





Cavity field and phase droop with feedback alone (left) and feedback + feedforward (right) beam loading compensation.



Phase width of the bunch along the pulse with feedback alone (left) and feedback + feedforward (right).

Phase width in CCL is larger than design value.


# Simulated beam envelope compared to Carbon wire scanners results in DTL and CCL




# Mode Locked Laser

## First Longitudinal Measurements

2.5 MeV H<sup>-</sup>, 402.5 MHz bunching freq, TiSapphire laser phase-locked @ 1/5<sup>th</sup> bunching freq;



collected electron signal plotted vs. phase




Measured and predicted bunch length vs. cavity phase setting



# Global view provided by Channel 13

## An example supervisory layer application



W. Blokland  
M. Sundaram  
C. Long

# Complete Linac: 326 Devices

## Commissioning begins late summer 2005



**MEBT**

- 6 Position
- 2 Current
- 5 Wires
- 2 Thermal Neutron
- 1 Emittance Horizontal
- 1 Emittance Vertical
- 1 Fast Faraday Cup
- 1 Mode-locked Laser
- 1 Faraday/Beam Stop
- D-box video
- D-box emittance
- D-box beam stop
- D-box aperture
- Differential BCM

**CCL**

- 10 Position 9 Wire
- 8 Neutron, 3 BSM,
- 2 Thermal
- 28 Loss 3 Bunch
- 1 Faraday Cup 1 Current
- 1 Dump

**DTL**

- 10 Position 5 Wire 12 Loss
- 5 Faraday Cup 6 Current
- 6 Thermal and 12 PMT Neutron
- Differential BCM

**CCL/SCL Transition**

- 2 Position 1 Wire
- 1 Loss 1 Current

**SCL**


- 32 Position 86 Loss
- 8 Laser Wire
- 7 PMT Neutron

**HEBT**


- 11 Position
- 5 Wire
- 17 BLM, 3 FBLM
- 2 Current

**LDump**

- 6 Loss
- 6 Position
- 1 Wire ,1 BCM



# Ring then to Target: 602 Devices Commissioning in first half of 2006



# Summary

---



- The SNS Diagnostics Team has deployed a variety of instruments that is unprecedented at this stage of commissioning.
- Interleaving commissioning and installation has been challenging, but based on experience from early commissioning runs, several systems have already been added or upgraded.
- System readiness, controls integration, and general performance has been outstanding.
- 50% of our beam instrumentation is installed; 25% is commissioned with beam.
- All partner laboratories have completed their work and Oak Ridge now has full responsibility.
- It will be a busy year.